BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of work: Providing and Fixing Sign boards in Hegadenagara Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	30.62	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	86.92	
2	7.65	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete	cum	5159.02	
3	22.96	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete	cum	5598.92	
4	252.00	Providing MS Pipe Name Board Made 3" (75mm) Dia M.S Pipe for verticalpole and 3 Nos of Horizontal Support pipe of 11/2" (38") dia pipe each of Length 1m signage board of size 60X45 cm and 60X23 cm size made of 16 guage M.S Sheet welded to M.S Square tube frame of size 25X25 mm all manual are cut size and all items electricals welded as per the drawing all joints are grinded smooth and painted with 2 cots of approved colour synthetic enamel paint over a coat of industrical prime and painting the required detail in fountain on either side of board as per the details provided etc complete.	No.	6506.00	
5	45360.00	KSRRBM800-10 Painting New letter and Figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specification. ("II) English and Roman Hyphen and the line not tobe measured and Piad for	No.	0.45	

No corrections - sd/ 24/04

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

24/04

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

24/4/17